

Bruhath Bangalore Mahanagara Palike Dasarahalli Zone

Name of Work: Construction of RCC drain in 3rd and 5th cross roads south side at Prashanthnagara, in ward no.13, in Shettyhalli Sub-Division

Est .Cost Rs. 27.30 Lakhs

SI No	Description of Items	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRRB 300-3. Earthwork excavation by manual means in ordinary soil involving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. Page No. 141/ Item No. 19.1/ PWD SR 2015-16								
	3rd cross - RCC drain	Cum							
	From Muthurayaswamy temple to dead end		2	155.00	0.90	0.75	209.25		
	5th cross S/s - RCC drain		1	175.00	0.90	0.75	118.13		
							327.38	83.16	27225.00
	Basic Rate	77.00							
	Area Weightage @ 8%	6.16							
		83.16							
2	KSRB 4-1.2: Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS : 4.1, 4.2 Page No. 12/ Item No. 4.2/ PWD SR 2015-16	Cum							
	RCC Drain		2	155.00	0.85	0.15	39.53		
			1	175.00	0.90	0.15	23.63		
							63.15	5139.94	324587.00
	Basic Rate	4849.00							
	Area Weightage @ 6%	290.94							
	Total	5139.94							
3	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1, 4.5 ,P.13/I.4.11/ PWD SR 2015-16								
	Walls	Cum	2x2	155.00	0.13	0.70	56.42		
	Bed		2	155.00	0.70	0.13	28.21		
			1x2	175.00	0.13	0.70	30.63		
			1	175.00	0.70	0.130	15.93		
			2	140.00	0.80	0.150	33.60		
			1	170.00	0.80	0.150	20.40		

[illegible]

	Qty Vide Item No=1+2	Cum					327.38		
	Qty Limited to						355.00	81.73	29016.00
	(For 3 km = 3 x 1.28 x 2.0)	7.68							
	Loading and Unloading Charges	68.00							
		75.68							
	Area Weightage @ 8%	6.05							
	Total	81.73							
								Sub Total	2702871.00
8	Add Quality control charges @1%								27000.00
9	Miscellaneous and unforeseen Charges								196.00 129.00
								Total	2730000

(Rupees Twenty seven thirty thousand Lakhs Only)

- 1 The Work spot has been inspected and the work found to be necessary
- 2 The Estimate is prepared as per the PWD SR 2015-16
- 3 The Provision made in estimate are adequate and essential
- 4 This area comes under BBMP limits.

(Ct) / D2/D5 / 16 / 15/11
P941
RS (2730000/-)
Date: 04/01/2016
Signature